

Tips for using exposed-concrete vibrators AR 36/6/042 and ARFU 36/6/230

Fastening the vibrators in place:

- Tighten the fastening system firmly.
- Attach the fall safety device.
- Check regularly to make sure the vibrators is fastened properly.

The vibrators' running time on the formwork:*


- Compaction time: about 3 ... 5 minutes for every layer of concrete that is added
- Normally switch on exposed concrete only after the first compacted backfill layer has been completed.
- Maximum fill height: 50 cm

Equipping forms with exposed-concrete vibrators:*


- Forms can be fully equipped with vibrators. If they are not, the vibrators must be shifted - we recommend working with at least two rows.
- If both sides of the forms are equipped with vibrators and the wall thickness is less than 50 cm, the vibrators should be arranged in an alternating pattern (not directly across from each other), if possible.



42V multi-plug receptacle for using AR 33/6/042 on frequency converter.



Equipping frame-type forms



* This information is the result of practical experience. The best configuration may vary under special conditions and with special types of concrete. We recommend testing a sample first.




www.wackergroup.com



Tips for using exposed-concrete vibrators AR 36/6/042 and ARFU 36/6/230

Equipping the forms and the effective compaction depth of exposed-concrete vibrators (side view):



* This information is the result of practical experience. The best configuration may vary under special conditions and with special types of concrete. We recommend testing a sample first.

